



Treatment Notes

Rehabilitation – LCB: Includes the Removal of existing Road, Repairing of any base defects, culverts, ditching, gravel and surface treatment (even if it occurs in the next year)

Reconstruction – HCB: Is currently a lump sum which represents the full depth excavation of the Road, replacement of underground, rebuild and sidewalks if applicable. With greater knowledge of the associated assets these costs can be refined (i.e. separate costs for sidewalks, water, storm system components)

Mill and Pave: Milling of a required depth of asphalt to assure that proper grading and drainage is maintained prior to new overlay surface.

